


## 260.2400 | 4-Hole Deck Mounted Roman Tub Filler With Hand Held Shower





## SPECIFICATIONS:

- Solid Brass construction includes valves
- Four Hole Installation
- Flow Rate = 8.5 GPM @ 60 PSI
- Hand Shower Flow Rate = 1.8 GPM @ 60 PSI
- Diverter handle controls water flow between spout and hand held

## STANDARDS:

ASME A112.18.1 / CSA B125.1

**Legislation Compliance** 



ZeroDrip Technology



